

The Common Portions will be completed and finished as follows:

Super -	RCC framed structure with Monolithic concrete.
Structure	The state of details with Monontine Concrete.
Brick Work	External Wall: 8 inch thick with cement mortar (1:6) using 1 <sup>st</sup> class clay/block brick.  Partition Wall: 5 inch thick brickwork with cement mortar in proportion (1:6) by using 1 <sup>st</sup> class clay/block bricks.
Plaster	Wall Plaster outside surface 12mm thick (1:6 cement mortar), Inside plaster 12mm thick (1:6 cement mortar) Ceiling Plaster 6mm thick (1:4 cement mortar)
Stair Case	Staircase and lobby will be finished with good quality vitrified tiles and
And Lobby	Staircase with mild steel railing.
Drainage	The drainage connection will be done as per approved drawing of Plumbing Engineer with very good quality material. Rain water pipes will be 6"/4" India made of supreme or equivalent brand.
Roof	Good quality material will be laid on roof or plain cement concrete with
Treatment	necessary water proofing admixture.
Water	Water supply with high quality pumps and deep tubewell boring will be
Supply	made available.
Electrical	Transformer and Mother Meter will be provided upon completion of procedure and payment of security deposit to WBSEDCL. Electrical mains etc. will be provided with good quality copper wire and light surround the project.
Painting	Outside face of external walls will be finished with high quality weather
And	coat. Gates and staircase railing grills will be painted with two coats of
Finishing	enamel paints over of primer.
Elevators	Manual Lifts as per Sanction Plan for each Block.

The Said Unit will be completed and finished as follows:		
Floor Of	<ul> <li>Glazed vitrified tiles in all bedrooms, living/dining rooms, kitchen,</li> </ul>	
Rooms And	balcony and Toilets Anti-skid ceramic tiles.	
Toilets	, and the same same same same same same same sam	
Kitchen and	<ul> <li>Kitchen: Ceramic tiling upto 2.5 feet from the granite counter tops</li> </ul>	
Toilet Walls	with steel sink.	
	<ul> <li>Toilet: Ceramic tiles up to 6.5 feet/up to soffit of lintel level.</li> </ul>	
	<ul> <li>Door frames will be made of good quality shal wood.</li> </ul>	
	Shutters will be pressed good quality flush door and hatch	
Doors	bolt/Aldrop.	
	Mortise lock/Cylindrical lock in the door and night latch for the	
	main door of the Unit will be provided.	
Windows	Fully Aluminium windows with glass fittings and standard handle.	
Sanitary	The following will be provided:	
Fittings In	Tap and shower arrangements.	
Toilet/s	Light colored European type water closet made of porcelain.	
Tonet/S	Water pipe line.	

LLP IN: ACA-1645

	Hot and cold water line.
	The state of the s
	<ul> <li>Provision for installation of geysers (only Common Bath room).</li> </ul>
	<ul> <li>Light colored wash basin made of porcelain (only Common Bath</li> </ul>
	room).
	,
	best data solution with good quality copper who will be provided.
	<ul> <li>TV Power points in living /dining.</li> </ul>
Electrical	Adequate electrical points in all bedrooms, living /dining, kitchen
Points And	and toilets.
Fittings	Refrigerator and Geyser point
	<ul> <li>Modular switches of reputed make</li> </ul>
	<ul> <li>Calling bell point for the main door of the Unit.</li> </ul>
Intercom	Telephone points will be provided in the living room with connection of
	intercom for each individual Unit of the complex.
Wall	Internal face of the walls will be finished with good quality wall putty.
Finishing	

SLISH- KUPL.

Designated Partner