



TYP. FL SHUTTERING LAYOUT (2ND-27TH)

- SPECIFICATIONS:-**
- ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE STATED.
 - ALL EXTERNAL WALLS ARE 200 TH. & ALL INTERNAL WALLS ARE 125 TH.
 - THE DEPTH OF S.U.G.W.R. & SEPTIC TANK SHALL NEVER EXCEED THE DEPTH OF FOUNDATION.
 - BRICK WORK 200 TH. MORTAR 1:6 & BRICK WORK 125 TH. MORTAR 1:4
 - ALL R.C.C. WORKS EXCEPT FOUNDATION M35
 - GRADE OF STEEL FE 415 I.S. CODE 1786/1978
 - ALL SHORTS OF PRECAUTIONARY MEASURE WILL BE TAKEN AT THE TIME OF CONSTRUCTION
 - OTHERS ITEM ARE AS PER I.S. SPECIFICATION

DECLARATION OF GEO-TECHNICAL ENGINEER:-

UNDERSIGNED HAS INSPECTED THE SITE AND CARRIED OUT SOIL INVESTIGATION THEREON, IT IS CERTIFY THAT THE EXISTING SOIL OF THE SITE IS ABLE TO CARRY THE LOAD COMING FROM THE PROPOSED CONSTRUCTION AND THE FOUNDATION SYSTEM PROPOSED HEREIN IS SAFE AND STABLE IN ALL RESPECT FROM GEO-TECHNICAL POINT OF VIEW

Jishnu Pal
JISHNU PAL
 B.Tech (Civil), M.E. (Geo-tech)
 K.M.C Reg. No. G-171/32
 C.T.E.R./NKDA/10/0043
 22/RJSON/G-T-1/2016-17
 H.M.C Reg. No. EGTB/CLASS-1/15

SIGNATURE OF GEO-TECHNICAL ENGG.

I HAVE REVIEWED / CHECKED THE STRUCTURAL DRAWING AND DESIGN DETAILS OF THIS PROJECT WHICH HAS BEEN DONE COMPLYING RELEVANT I.S. CODE INCLUDING SEISMIC AND THE NATIONAL BUILDING CODE. I CERTIFY THAT THE STRUCTURE WILL BE SAFE & STABLE AGAINST ALL VERTICAL AND LATERAL LOADS AND WILL BE FIT FOR HABITABLE USE.

Utpal Santra
UTPAL SANTRA
 B.C.E. M.C.E. (STRUCT)
 F.I.E. - F1212601
 K.M.C Empowered Structural Reviewer
 E. S. R. - (I) 58/10

SIGN OF STRUCTURAL REVIEWER

CERTIFICATE OF STRUCTURAL ENGINEER.

THIS IS TO CERTIFY THAT THE STRUCTURAL DESIGN AND DRAWING OF BOTH FOUNDATION AND SUPER STRUCTURE OF THE BUILDING HAS BEEN MADE BY ME CONSIDERING ALL POSSIBLE LOADS INCLUDING THE SEISMIC LOADS AS PER THE NATIONAL BUILDING CODE OF INDIA AND CERTIFIED THAT IT IS SAFE AND STABLE IN ALL RESPECTS.

Sumita Dey
SUMITA DEY
 M.C.E., M.I.E., C.E.
 ESE/1/93

SIGNATURE OF STRUCTURAL ENGG.

WE DO HEREBY UNDERTAKE WITH FULL RESPONSIBILITY THAT - (1) WE SHALL ENGAGE ARCHITECT & E.S.E. DURING CONSTRUCTION. (2) WE SHALL FOLLOW THE INSTRUCTION OF ARCHITECT & E.S.E. DURING CONSTRUCTION OF THE BUILDING (AS PER PLAN 1, 3) & M.C. AUTHORITY WILL NOT BE RESPONSIBLE FOR STRUCTURAL STABILITY OF THE BUILDING & ADJOINING STRUCTURE. (4) IF ANY SUBMITTED DOCUMENTS ARE FOUND TO BE FAKE, THE K.M.C AUTHORITY WILL RESERVE THE SANCTION ON (1) THE CONSTRUCTION OF WATER RESERVOIR AND SEPTIC TANK WILL BE UNDER THE GUIDANCE OF ARCHITECT & E.S.E.

For Kolkata Metropolitan Development Authority

Prasad Sharma
 (Hrati Prasad Sharma)
 Constituted Attorney

SIGNATURE OF OWNER

I HEREBY CERTIFY THAT THE ERECTION OF BUILDING ON PREMISES NO. P-10 C.T. SCHEME III, KOLKATA-700045 UNDER MY SUPERVISION, I ALSO CERTIFY THAT THE PROPOSED CHANGES IN LAYOUT HAS BEEN DRAWN AS PER PROVISION OF K.M.C BUILDING RULES 2008.

Subir Kumar Basu
SUBIR KUMAR BASU
 Registered Architect
 Regn. No. - CA/78/4375

SIGNATURE OF ARCHITECT

PROJECT-
 PROPOSED ADDITION OF 4 NOS. FLOOR (HT. -100.1 M.) OVER AN EXISTING B+G+27 STORED(3 NOS TOWERS) RESIDENTIAL BUILDING WITH PODIUM AND G+V+G+VI STORED REHABILITATION BLOCK U/S 394 OF K.M.C. ACT 1980 READ WITH 69A (7)(a) ALONG WITH U/R 25(2)(b), (26) OF K.M.C. BUILDING RULE 2009 AT PREMISES NO. P-10 C.T. SCHEME III (M), MANCKTALA, WARD - 32, BOROUGH III KOLKATA -700 054.

PREVIOUS B.P. NO. 2012030110, DATED 23.03.13.
 SUBSEQUENTLY REVALIDATED FURTHER 5 YEARS

Architect:
 Subir Kumar Basu
 CONSULTING ARCHITECTS & ENGINEERS
 4 BROAD STREET KOLKATA - 700019
 website : www.subirkumarbasu.com

Civil & Structural Consultants:
M.N. CONSULTANTS (Pvt) Ltd.
 MNC HOUSE
 1515, RAJANCA MAIN ROAD
 KOLKATA - 700 107
 Ph.no.-913324418082/913340165700
 FAX NO. 913324418083
 E-MAIL: mncopl2008@gmail.com



Title:
 TYP. FL SHUTTERING LAYOUT (TOWER-01,02&03)

| | | |
|-----------------|----------------------------------|--------------------|
| Drawn A.M | Scale:- AS SHOWN | Date 10.10.2023 |
| Job No. 2338 | Drawing No. CORP-T1-S20-06-01 | |

PARTY'S COPY

Structural plan and design calculation as submitted by the structural engineer have been kept with B.P. No. 2023-23-00-53. Date 13-10-2023 for record of the Kolkata Municipal Corporation without verification. No deviation from the submitted structural plan should be made at the time of erection without submitting fresh structural plan along with design calculation and stability certificate in the prescribed form. Necessary steps should be taken for the safety of the adjoining premises public and private properties and safety of human life during construction.

[Signature]
EXECUTIVE ENGINEER/ASST. ENGINEER
BOROUGH NO. - 6

Necessary steps should be taken for the safety of the lives of the adjoining public and private premises during construction.

RESIDENTIAL BUILDING

Building Department
Borough-III, K.M.C.
Date: 13-10-23, Signed: *[Signature]*
Contents Not Verified