




PROJECT
PROPOSED G+12 STOREYED AFFORDABLE HOUSING UNDER PRADHAN MANTRI AWAS YOJANA AT MUNICIPAL HOLDING NO. 31, KANAILAL GOSWAMI SARANI, UNDER CIRCLE NO. 'F', OF THE SERAMPORE MUNICIPALITY COMPRISED IN L.R. DAG NOS. 2588, 2589, 2597, 2598, 2603, 2604, 2605, 2607, 2608, 2609, 2610, 2611, 2612, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2631, 2642, MOUZA: MAHESH, P.S. SERAMPORE, J.L.: 15, L.R. KHATIAN NO. 11337, P.O. SERAMPORE, PIN: 712201, DISTRICT HOOGHLY, WEST BENGAL.

OWNER :
EDEN REALITY PVT. LTD

TITLE :

FIRST AND SECOND FLOOR PLAN (TYPE-10)

SCHEDULE OF DOORS & WINDOWS					
DOORS			WINDOWS		
TYPE	WIDTH	HEIGHT	TYPE	WIDTH	HEIGHT
D1	1000	2100	W1	1200	1200
D2	900	2100	W2	1000	1200
D3	750	2100	W3	900	900
D4	2000	2100	W4	600	900
SD1	2250	2100	W5	750	1200
SD2	2550	2100	W6	800	425
SD3	2850	2100	W7	600	425

- SPECIFICATION**
1. ALL DIMENSIONS ARE IN MM UNLESS IT IS MENTIONED
 2. ALL EXTERNAL BRICK WALLS ARE 200 MM THICK AND INTERNAL 100 MM THICK.
 3. ALL BRICKWORK PLASTERING INSIDE OR OUTSIDE ARE IN THE RATIO OF 1:6 & 1:4 RESPECTIVELY AND OUTSIDE PLASTERING CONTAINS WATER PROOFING
 4. ALL CIVIL WORKS ARE AS PER IS 456 AND ALL REINFORCEMENT AS PER IS 1176.
 5. ALL R.C.C. WORKS ARE IN THE RATIO M-25
 6. ALL PRECAUTIONARY MEASURES SHALL BE TAKEN AT THE TIME OF CONSTRUCTION
 7. DEPTH OF WATER RESERVOIR SHALL NOT BE MORE THAN THE DEPTH OF MAIN COLUMN FOUNDATION

EDEN INFRACON PRIVATE LIMITED
Director
CONSTITUTED ATTORNEY OF PYRAMID ENCLAVE (P) LTD.

SIGNATURE OF OWNER
WE DO HEREBY CERTIFY THAT THE FOUNDATION AND SUPERSTRUCTURE OF THE BUILDING PROPOSED FOR CONSTRUCTION ON PREMISES NO. 31, KANAILAL GOSWAMI SARANI PREVIOUSLY KNOWN AS DAMODAR ROAD UNDER CIRCLE NO. 'F', OF THE SERAMPORE MUNICIPALITY COMPRISED IN L.R. DAG NOS. 2588, 2589, 2597, 2598, 2603, 2604, 2605, 2607, 2608, 2609, 2610, 2611, 2612, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2631, 2642, MOUZA: MAHESH, P.S. SERAMPORE, J.L.: 15, L.R. KHATIAN NO. 11337, P.O. SERAMPORE, PIN: 712201, DISTRICT HOOGHLY, WEST BENGAL HAVE BEEN SO DESIGNED BY ME/AS/WE/ALL MAKE SUCH FOUNDATION AND SUPERSTRUCTURE SAFE IN ALL RESPECT INCLUDING THE CONSIDERATION OF BEARING CAPACITY AND SETTLEMENT OF SOIL ETC.

SIGNATURE OF REGISTERED ENGINEER
GEOTEST ENGINEERS PVT. LTD.
ALOK ROY
CITE-1/71
6A, MILTON PARK, GARIAHAT, KOLKATA-700084.

SIGNATURE OF STRUCTURAL ENGINEER
BREK BRASHI MULLICK
BREK BRASHI MULLICK
B.E. (CIVIL), M.E. (STRUCTURES)
P.O. BOX - 1070 (S.S. 34.5.1)
Kolkata - 700 011

SIGNATURE OF ARCHITECT
MALAY KUMAR GHOSH
Regn. No. CA/92/14854
35A, Dr. Sarat Banerjee Road
Kolkata - 700 029

SCALE
1:100
DATE: 30.07.18
DRAWN: P.B.S.B.
CHECKED: M.G.

ARCHITECTS
SPACE
35A, DR. SARAT BANERJEE ROAD,
KOLKATA 700-029
PIN-700-029

THIS DRAWING IS A PROPERTY OF SPACE. 35A, DR. SARAT BANERJEE ROAD, KOLKATA-700 029. ANY MODIFICATION CHANGES, DEVIATIONS IS NOT PERMISSIBLE WITHOUT PRIOR INTIMATION TO SPACE. IN THE CONTRARY, THIS WILL BE TREATED AS ILLEGAL ACT.

Petition No. 754 of 2018-19
Permission for the new construction as
proposed and shown in the plan is granted
Value No. 15.00 and corresponding
B.O.C. Meeting Date 25.11.2018
Dated 17/01/18 Chairman

Serampore Municipality

1. This plan is valid for three years and may
be revaluated for the further two years on
payment of necessary charges with production
of original plan allowing with prescribed form.
2. Within one month after the completion of new
construction or a suitable portion thereof, the
owner must be informed this to the Municipal
Authority for interim assessment on a prescribed
form.

Chandrasekar Chakrabarti
Urban Infrastructure Expert
Serampore Municipality

Nikhil Kumar Banerjee
Technical Advisor & Consulting
Engineer
Retd. Chief Engineer M.E.D.
Serampore Municipality

ARCH-10-02
(TYPE -10)
1ST FLOOR PLAN