

SCHEDULE OF WORK
(SPECIFICATION OF THE BUILDING CONSTRUCTION)

All Civil Work as per I.S.I. standard.

1. Floor tiles/Marble in Bed Room, Drawing and Dining Room,
2. Marble flooring in Kitchen, Toilet & W.C.
3. Sal Wood Door frame.
4. Factory made ply Flush Door Shutter.
5. Aluminium window (with Grill)
6. Putty in inside wall.
7. Putty in staircase & Weather coat paint in Car Parking Space.
8. Glazed tiles Up to 6 ft. height in toilet & W.C. wall. Tiles upto beam bottom height in kitchen on granite kitchen platform.
9. Concealed Electrical wiring with copper wires, Two Light point and Fan, Plug point one each in Bed Room, Drawing/Dining Room, 15A plug point in Drawing/Dining & Toilet.
10. Concealed water supply line of Supreme brand or equivalent.
11. White pan, basin & commode in toilet.
12. Stainless Steel sink in Kitchen.
13. Granite platform in kitchen.
14. Synthetic enamel paint in door shutter and grill.
15. Weather coat on outside wall.
16. Essco make bib cock, stop cock.
17. OTIS Lift shall be installed.

It is noted that if any extra work is done as per the desire of the PURCHASER, for such extra work, the PURCHASER shall pay the necessary cost to the DEVELOPER.

SHELTERCON

Arinadha Venkatesh

Proprietor